



Coordinate Table				
Station	Eastings	Northings	Level	Description
S1	500.000	1050.000	50.000	Flag
S2	481.165	977.895	49.917	Flag
S3	508.037	1053.228	50.119	Flag
S4	502.121	947.023	50.118	Flag
S5	493.289	973.775	49.991	Nail in stump
S6	600.336	984.725	49.989	Nail in stump

**Note**

This survey data has been prepared for the client detailed below to an agreed specification. Unless otherwise agreed in writing the liability of 360 Geomatics Ltd is limited to the client or his appointed agent and does not extend to use beyond the limitations of the specification.

Survey is based on an arbitrary grid.

All levels are related to a local site datum located at S1 Value 50.000m.

All levels on kerb lines are channel levels unless noted otherwise.

Water level taken on the 23rd of February, value 48.83m.

© Copyright 360 Geomatics Ltd 2014

Abbreviations (Where Applicable)	
ACU	Air Conditioning Unit
AB	Assemed Route
BB	Bellwre Beacon
BRL	Bore Hole
BL	Borehole Light
BO	Bolford
BP	Block Paving
BRW	Brick Retaining Wall
BS	Bus Stop
BSH	Bus Shelter
BT	BT Inspection Cover
CB	Control Box
CCTV	Closest Circuit Television
CL	Cover Level
Co	Column
Conc	Concrete
CPS	Concrete Paving Slabs
CS	Cablestones
CT	Cable TV Inspection Cover
Ch	Concrete (In situ)
DC	Drainage Channel
DK	Drop Kerb
DR	Down Pipe
EJB	Electric Junction Box
EP	Electricity Pole
ES	Earthed Rod
FB	Flower Bed
FL	Flushed Floor Level
FI	Fire Hydrant
FL	Flood Light
FP	Fuel Pump
FMMH	Foul Water Manhole
G	Girth (ø)
CC	Concrete
GU	Gully
OV	Over Valve
B	Burtonhole Borehole
IC	Inspection Cover
L	Level
KO	Kerb Outlet
LB	Litter Bin
LP	Lamp Post
MC	Masonry Inspection Cover
MI	Manhole
MH	Masonry High
MK	Marker Post
MSP	Manicured Street Tree
NB	Notice Board
NI	No Further Information
NP	Street Name Plate
OW	Overhead Wire
OSM	Ordnance Survey Bench Mark
PK	Particaban
PM	Parking Meter
PK	Particaban
PK	Parking Meter
RE	Reading Eye
RS	Road Sign
RW	Retaining Wall
S	Spread (In situ)
SI	Slit
SL	Slip Level
SP	Structure Post
SR	Stone Wall
ST	Slay Wire
TCP	Telephone Cill Box
TL	Threshold Level
TK	Top of Kerb Level
TD	Top of Wall
TF	Top of Fence
TW	Top of Wall
TP	Telephone Pole
TFS	Tactile Paving Slabs
UTL	Unable to Girth
UTL	Unable to Trace
UV	Under Valve
W	Water Level
WM	Water Meter
WO	Workout
WP	Waste Pipe
WV	Water Valve

Fence Types	
H/R	Hand Rail
I/R	Iron Rolling
O/B	Open Bordered
P/S	Palisade Security
P/R	Post and Rail
P/W	Post and Wire
W/W	Wire Mesh

Z Analysis			
Colour	Band	Area	
■	42.00	44.00	0.00%
■	44.00	44.50	0.42%
■	44.50	45.00	15.41%
■	45.00	45.50	14.96%
■	45.50	46.00	19.44%
■	46.00	46.50	7.41%
■	46.50	47.00	6.12%
■	47.00	47.50	5.62%
■	47.50	48.00	4.90%
■	48.00	48.50	5.32%
■	48.50	49.00	4.30%
■	49.00	49.50	4.41%
■	49.50	50.00	6.80%
■	50.00	50.50	0.00%
■	50.50	51.00	0.00%

Rev	Rev Suffix	Revision Details	Initial	Date

Surveyed by

**360GEOMATICS**  
 LAND & MEASURED BUILDING SURVEYS  
 10 Salters Heath Road  
 Monk Sherborne, Tadley  
 Hampshire RG26 5HY  
 Tel: 01256 851672  
 Mob: 07734 233459  
 Email: info@360g.co.uk  
 Website: www.360g.co.uk

Client:			
Job Title:			
Drawing Title:	TOPOGRAPHIC SURVEY		
Drawing No:	Rev Suffix:		
Drawn: IPB	Checked: DR	Scale: 1:200	Date:
Job No:	Sheet: 1 of 1	Sheet Size: A0	